



KAZI NAZRUL UNIVERSITY

Nazrul Road, Kalla More, P.O. – Kalla C. H.
Asansol – 713340, Dist.-Paschim Bardhaman, West Bengal
Website: www.knu.ac.in

Ref. No. : KNU/R/TENDER/1102/23

Date: 21/08/2023

TENDER NOTICE FOR CONSTRUCTION OF 12.5 MT. BOUNDARY WALL

Sealed Quotations (Rate per Unit) are invited from Authorised contractor having trade license and other relevant papers with GST NO. for **Construction of boundary wall at KNU Campus**. TERMS and CONDITIONS are given below. Quotations shall be submitted SEALED envelope with our REF. NO. and DATE duly super scribed on the COVER to the "Registrar, Kazi Nazrul University, Nazrul Road, Kalla Bypass More, P.O.- Kalla C.H., Asansol, West Bengal -713340."

Last date of submission of the completed application form either by hand or by post is on 02.09.2023 at 4.00 p. m.

Items Details:

Length of Boundary wall 12.5 mt.

SL NO	ITEMS OF WORK	QUANTITY	UNIT	RATE	AMOUNT (IN RS.) INCLUDING GST
1	Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within lead of 75m as directed. The items includes necessary trimming the Sides of trenches, levelling, dressing and ramming the bottom, balling out water as required complete (a) Depth of excavation not exceeding 1.500mm.	7.86	Cum		
2	Filling in foundation or plinth by silver sand in layers not exceeding 150 mm as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand	3.53	Cum		
3	Cement concrete with graded Stone chips (40 mm. size) excluding shuttering. In	0.60	Cum		



KAZI NAZRUL UNIVERSITY

Nazrul Road, Kalla More, P.O. – Kalla C. H.
Asansol – 713340, Dist.-Paschim Bardhaman, West Bengal
Website: www.knu.ac.in

	ground floor and foundation. (a) 1:3:6 proportion				
4	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20mm. Size) excluding shuttering and reinforcement, if any, in ground floor. (a) Pakur Variety	3.30	Cum		
5	Reinforcement for reinforced concrete work in all sorts of Structures including distribution bars, stirrups binders' etc. including supply of rods. Initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every inter-section, complete as per drawing and direction. Other than SAIL/ TATA/RIN	0.259	MT		
6	Hire and labour charges for shuttering with centering and necessary staging up to 4m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams, columns, lintels curved or straight including fitting, fixing and striking out after completion of works. (Up to roof of ground floor). 25 mm to 30 mm shuttering without staging in foundation	8.60	Sqm		
7	Hire and labour charges for shuttering with centering and necessary staging up to 4 m using approved stout props	17.35	Sqm		



KAZI NAZRUL UNIVERSITY

Nazrul Road, Kalla More, P.O. – Kalla C. H.
Asansol – 713340, Dist.-Paschim Bardhaman, West Bengal
Website: www.knu.ac.in

	and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and Striking out after completion of works (up to roof of ground floor) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge.				
8	125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor	17.00	Sqm		
9	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints or roughening of concrete surface, including throating, nosing and drip course where necessary (ground floor), With 1:4 cement mortar. 15 mm thick plaster	55.46	Sqm		
10	Applying Exterior grade Acrylic primer of approved quality and brand on plastered or concrete surface old or new surface to receive decorative textured (matt finish) or smooth finish acrylic exterior emulsion paint including scraping and preparing the surface thoroughly, complete as per manufacturer's Specification and as per direction of the EIC.	55.46	Sqm		
11	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of Engineer-in-Charge to be applied over acrylic primer as	55.46	Sqm		



KAZI NAZRUL UNIVERSITY

Nazrul Road, Kalla More, P.O. – Kalla C. H.
Asansol – 713340, Dist.-Paschim Bardhaman, West Bengal
Website: www.knu.ac.in

	required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer. b) Premium 100% Acrylic Emulsion				
--	--	--	--	--	--

SD/-
Registrar

For any query please contact registrar@knu.ac.in or visit the Registrar's Office from 2 PM. to 4 PM. on all working days before 23rd August 2023.

Terms & Conditions:

1. Place of work: Kazi Nazrul University, Asansol
2. The tenderers will not be entitled to ask for any further information other than whether their tenders have been received or not.
3. The University does not bind itself to accept the lowest or any tender or assign any reason for non- acceptance.
4. Self-attested copy of valid PAN, GST Registration Certificate, P Tax and Certificate of enlistment (Trade License) that may be required for construction Boundary wall must be provided by the bidders, failing which the bid may be rejected without assigning any reason thereof.
5. Deduction of all Taxes as per norms for each Bill/Invoice shall be made by the Authority at the time of payment.
6. The Tender Inviting Authority reserves the right to cancel the tender at any stage due to unavoidable circumstances and no claim in this respect will be entertained.
7. IN ALL CASES OF DISPUTES, THE DECISION OF THE UNIVERSITY SHALL BE FINAL & BINDING ON YOU.

By Order