



# KAZI NAZRUL UNIVERSITY

Nazrul Road, Kalla More, P.O. – Kalla C. H.  
Asansol – 713340, Dist.-Paschim Bardhaman, West Bengal  
Website: [www.knu.ac.in](http://www.knu.ac.in)

Ref. No. : KNU/R/TENDER/1105/23

Date: 21/08/2023

## TENDER NOTICE FOR CONSTRUCTION OF KITCHEN SHADE

Sealed Quotations (Rate per Unit) are invited from Authorised contractor having trade license and other relevant papers with GST NO. for **Construction of Kitchen shade at KNU Campus**. TERMS and CONDITIONS are given below. Quotations shall be submitted SEALED envelope with our REF. NO. and DATE duly super scribed on the COVER to the “**Registrar, Kazi Nazrul University, Nazrul Road, Kalla Bypass More, P.O.- Kalla C.H., Asansol, West Bengal -713340.**”

Last date of submission of the completed application form either by hand or by post is on **02.09.2023 at 4.00 p. m.**

SL NO	ITEMS OF WORK	QUANTITY	UNIT	RATE	AMOUNT (IN RS.) INCLUDING GST
1	Surface Dressing of the ground in any kind of soil including removing vegetation inequalities not exceeding 15 cm depth and disposal of the rubbish within a lead up to 75 m as directed.	8.00	Sqm		
2	Earth work in excavation of foundation trenches ordains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m.as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete. Depth of excavation not exceeding 1,500 mm	7.50	Cu.m		
3	Filling in foundation or plinth by silver sand in layers not exceeding 150 mm as directed and consolidating	0.90	Cu.m		



# KAZI NAZRUL UNIVERSITY

Nazrul Road, Kalla More, P.O. – Kalla C. H.  
Asansol – 713340, Dist.-Paschim Bardhaman, West Bengal  
Website: [www.knu.ac.in](http://www.knu.ac.in)

	the same by thorough saturation with water, ramming complete including the cost of supply of sand. (Payment to be made on measurement of finished quantity)				
4	Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work)	1.50	Cum		
5	Cement concrete with graded jhama khoa (30 mm size) excluding shuttering In ground floor and foundation. 1:2:4 proportion	1.00	Cum		
6	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, In Gr floor. as per relevant IS codes. (i) Pakur Variety	1.20	Cum		
7	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc. initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction	0.10	MT		



# KAZI NAZRUL UNIVERSITY

Nazrul Road, Kalla More, P.O. – Kalla C. H.  
Asansol – 713340, Dist.-Paschim Bardhaman, West Bengal  
Website: [www.knu.ac.in](http://www.knu.ac.in)

8	Hire and labour charges for shuttering with centering and necessary staging up to 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (up to roof of ground floor)	16.00	Sq.M		
9	Brick work with 1st class bricks in cement mortar (1:6)				
	In foundation and plinth	0.60	Cum		
	In superstructure, ground floor	1.00	cum		
10	M.S. structural works in roof trusses with tubular sections conforming to IS: 806-1968 & IS: 1161- 1998 connected to one another with bracket, gusset cleats as per design, direction of	0.12	MT		
11	Galvanised iron sheet ridging fitted with necessary bolts, screws, washers etc. complete. (225mm end lapping) (B) 450 mm lapping each way with 0.63 mm sheet	3.00	RM		
12	Galvanised corrugated iron sheet work (excluding the supporting frame work) fitted and fixed with 10 mm. dia J or L hook-bolts, limpet and bitumen washers and putty complete with 150 mm. end lap and one corrugation minimum side lap. (Payment to be made on area of	7.50	Sq.m		



# KAZI NAZRUL UNIVERSITY

Nazrul Road, Kalla More, P.O. – Kalla C. H.  
Asansol – 713340, Dist.-Paschim Bardhaman, West Bengal  
Website: [www.knu.ac.in](http://www.knu.ac.in)

	Plaster (to wall , floor , ceiling etc.) with sand and cement mortar including rounding off or chamfering comers as directed and raking out joints including throating, nosing and drip course, scaffolding / staging	50.00	Sq.m		
13	Neat cement punning about 1.5 mm thick in wall, dado, winder sill, floor etc. NOTE: Cement 0. 152 cu.m per 100 sq m	5.00	Sq.m		
14	M.S. gate of Jail type as per approved design made of strong M.S. frame work, intermediate stiffeners and round / square bars or angles. M.S. sheet (not less than 14 gauge) gussets, cleats etc. including necessary riveting, bolting, welding, locking and hanging arrangements, fitting and fixing complete as per	0.32	Quantal		
	a) Priming one coat on steel or other metal surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	3.20	Sqm		
15	Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary	3.20	Sqm		
16	Applying Interior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive Distemper/ Acrylic emulsion paint including scraping and	25.00	Sqm		



# KAZI NAZRUL UNIVERSITY

Nazrul Road, Kalla More, P.O. – Kalla C. H.  
Asansol – 713340, Dist.-Paschim Bardhaman, West Bengal  
Website: [www.knu.ac.in](http://www.knu.ac.in)

	preparing the surface thoroughly, complete as per manufacturer's specification and as per direction of the EIC.				
17	Applying Exterior grade Acrylic primer of approved quality and brand on plastered or concrete surface old or new surface to receive decorative textured (matt finish) or smooth finish acrylic exterior emulsion paint including scraping and preparing the surface thoroughly, complete as per manufacturer's specification and as per direction of the EIC. In Ground Floor: (a) One Coat	25.00	Sqm		
18	Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer's specification) including cleaning and smoothing of surface. Two Coats	25.00	Sqm		
19	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of Engineer-in Charge to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer. In Ground floor (Two Coat) a) Normal Acrylic Emulsion	25.00	Sqm		
20	Artificial stone in floor, dado, staircase etc. with cement concrete (1:2:4) with stone chips, laid in panels as directed with topping made	7.30	Sqm		





# KAZI NAZRUL UNIVERSITY

Nazrul Road, Kalla More, P.O. – Kalla C. H.  
Asansol – 713340, Dist.-Paschim Bardhaman, West Bengal  
Website: [www.knu.ac.in](http://www.knu.ac.in)

with ordinary or white cement (as necessary) and marble dust in proportion (1:2) including smooth finishing and rounding off corners including raking out joints or roughening of concrete surface and application of cement slurry before flooring works using cement @ 1.75 kg/sq.m all complete including all materials.				
---	--	--	--	--

SD/-  
Registrar

For any query please contact [registrar@knu.ac.in](mailto:registrar@knu.ac.in) or visit the Registrar's Office from 2 PM. to 4 PM. on all working days before 23<sup>rd</sup> August 2023.

## Terms & Conditions:

1. Place of work: Kazi Nazrul University, Asansol
2. The tenderers will not be entitled to ask for any further information other than whether their tenders have been received or not.
3. The University does not bind itself to accept the lowest or any tender or assign any reason for non- acceptance.
4. Self-attested copy of valid PAN, GST Registration Certificate, P Tax and Certificate of enlistment (Trade License) that may be required for construction work must be provided by the bidders, failing which the bid may be rejected without assigning any reason thereof.
5. Deduction of all Taxes as per norms for each Bill/Invoice shall be made by the Authority at the time of payment.
6. The Tender Inviting Authority reserves the right to cancel the tender at any stage due to unavoidable circumstances and no claim in this respect will be entertained.
7. IN ALL CASES OF DISPUTES, THE DECISION OF THE UNIVERSITY SHALL BE FINAL & BINDING ON YOU.

By Order